

COMPRESSOR DATA SHEET

CAP710-NXHE132-100

Rotary Compressor: Fixed Speed

| MODEL DATA - FOR COMPRESSED AIR | | | |
|---------------------------------|--|---------------------------------------|-------------------------|
| 1 | Manufacturer: FS Curtis | | |
| 2 | Model Number: NxHE132A-100 | | Date: 6/19/2018 |
| | <input checked="" type="checkbox"/> Air-cooled | <input type="checkbox"/> Water-cooled | Type: Screw |
| | <input checked="" type="checkbox"/> Oil-injected | <input type="checkbox"/> Oil-free | # of Stages: 2 |
| 3* | Rated Capacity at Full Load Operating Pressure ^{a, e} | 983.3 | acfm ^{a, e} |
| 4 | Full Load Operating Pressure ^b | 100 | psig ^b |
| 5 | Maximum Full Flow Operating Pressure ^c | 101 | psig ^c |
| 6 | Drive Motor Nominal Rating | 180 | hp |
| 7 | Drive Motor Nominal Efficiency | 96.2 | percent |
| 8 | Fan Motor Nominal Rating (if applicable) | 5.5 | hp |
| 9 | Fan Motor Nominal Efficiency | 89.5 | percent |
| 10* | Total Package Input Power at Zero Flow ^e | 65.1 | kW ^e |
| 11 | Total Package Input Power at Rated Capacity and Full Load Operating Pressure ^d | 156.7 | kW ^d |
| 12* | Specific Package Input Power at Rated Capacity and Full Load Operating Pressure ^e | 15.9 | kW/100 cfm ^e |

*For models that are tested in the CAGI Performance Verification Program, these items are verified by the third party administrator.

Consult CAGI website for a list of participants in the third party verification program: www.cagi.org

- NOTES:
- a. Measured at the discharge terminal point of the compressor package in accordance with ISO 1217, Annex C; ACFM is actual cubic feet per minute at inlet conditions.
 - b. The operating pressure at which the Capacity (Item 3) and Electrical Consumption (Item 11) were measured for this data sheet.
 - c. Maximum pressure attainable at full flow, usually the unload pressure setting for load/no load control or the maximum pressure attainable before capacity control begins. May require additional power.
 - d. Total package input power at other than reported operating points will vary with control strategy.
 - e. Tolerance is specified in ISO 1217, Annex C, as shown in table below:

Member:



| Volume Flow Rate at specified conditions | | Volume Flow Rate | Specific Energy Consumption | No Load / Zero Flow Power |
|--|-----------------------|------------------|-----------------------------|---------------------------|
| m ³ / min | ft ³ / min | % | % | |
| Below 0.5 | Below 15 | +/- 7 | +/- 8 | +/- 10% |
| 0.5 to 1.5 | 15 to 50 | +/- 6 | +/- 7 | |
| 1.5 to 15 | 50 to 500 | +/- 5 | +/- 6 | |
| Above 15 | Above 500 | +/- 4 | +/- 5 | |

ROT 030

COMPRESSOR DATA SHEET

CAP710-NXHE110-125

Rotary Compressor: Fixed Speed

| MODEL DATA - FOR COMPRESSED AIR | | | |
|---------------------------------|--|---------------------------------------|-------------------------|
| 1 | Manufacturer: FS Curtis | | |
| 2 | Model Number: NxHE132A-125 | | Date: 6/19/2018 |
| | <input checked="" type="checkbox"/> Air-cooled | <input type="checkbox"/> Water-cooled | Type: Screw |
| | <input checked="" type="checkbox"/> Oil-injected | <input type="checkbox"/> Oil-free | # of Stages: 2 |
| 3* | Rated Capacity at Full Load Operating Pressure ^{a, e} | 883.3 | acfm ^{a, e} |
| 4 | Full Load Operating Pressure ^b | 125 | psig ^b |
| 5 | Maximum Full Flow Operating Pressure ^c | 126 | psig ^c |
| 6 | Drive Motor Nominal Rating | 180 | hp |
| 7 | Drive Motor Nominal Efficiency | 96.2 | percent |
| 8 | Fan Motor Nominal Rating (if applicable) | 5.5 | hp |
| 9 | Fan Motor Nominal Efficiency | 89.6 | percent |
| 10* | Total Package Input Power at Zero Flow ^e | 64.8 | kW ^e |
| 11 | Total Package Input Power at Rated Capacity and Full Load Operating Pressure ^d | 156.0 | kW ^d |
| 12* | Specific Package Input Power at Rated Capacity and Full Load Operating Pressure ^e | 17.7 | kW/100 cfm ^e |

*For models that are tested in the CAGI Performance Verification Program, these items are verified by the third party administrator.

Consult CAGI website for a list of participants in the third party verification program: www.cagi.org

- NOTES:
- a. Measured at the discharge terminal point of the compressor package in accordance with ISO 1217, Annex C; ACFM is actual cubic feet per minute at inlet conditions.
 - b. The operating pressure at which the Capacity (Item 3) and Electrical Consumption (Item 11) were measured for this data sheet.
 - c. Maximum pressure attainable at full flow, usually the unload pressure setting for load/no load control or the maximum pressure attainable before capacity control begins. May require additional power.
 - d. Total package input power at other than reported operating points will vary with control strategy.
 - e. Tolerance is specified in ISO 1217, Annex C, as shown in table below:

Member:



| Volume Flow Rate at specified conditions | | Volume Flow Rate | Specific Energy Consumption | No Load / Zero Flow Power |
|--|-----------------------|------------------|-----------------------------|---------------------------|
| m ³ / min | ft ³ / min | % | % | |
| Below 0.5 | Below 15 | +/- 7 | +/- 8 | +/- 10% |
| 0.5 to 1.5 | 15 to 50 | +/- 6 | +/- 7 | |
| 1.5 to 15 | 50 to 500 | +/- 5 | +/- 6 | |
| Above 15 | Above 500 | +/- 4 | +/- 5 | |

ROT 030

COMPRESSOR DATA SHEET

CAP710-NXHE132-150

Rotary Compressor: Fixed Speed

| MODEL DATA - FOR COMPRESSED AIR | | | |
|---------------------------------|--|---------------------------------------|-------------------------|
| 1 | Manufacturer: FS Curtis | | |
| 2 | Model Number: NxHE132A-150 | | Date: 6/19/2018 |
| | <input checked="" type="checkbox"/> Air-cooled | <input type="checkbox"/> Water-cooled | Type: Screw |
| | <input checked="" type="checkbox"/> Oil-injected | <input type="checkbox"/> Oil-free | # of Stages: 2 |
| 3* | Rated Capacity at Full Load Operating Pressure ^{a, e} | 793.6 | acfm ^{a, e} |
| 4 | Full Load Operating Pressure ^b | 150 | psig ^b |
| 5 | Maximum Full Flow Operating Pressure ^c | 151 | psig ^c |
| 6 | Drive Motor Nominal Rating | 180 | hp |
| 7 | Drive Motor Nominal Efficiency | 96.2 | percent |
| 8 | Fan Motor Nominal Rating (if applicable) | 5.5 | hp |
| 9 | Fan Motor Nominal Efficiency | 89.5 | percent |
| 10* | Total Package Input Power at Zero Flow ^e | 64.9 | kW ^e |
| 11 | Total Package Input Power at Rated Capacity and Full Load Operating Pressure ^d | 156.2 | kW ^d |
| 12* | Specific Package Input Power at Rated Capacity and Full Load Operating Pressure ^e | 19.7 | kW/100 cfm ^e |

*For models that are tested in the CAGI Performance Verification Program, these items are verified by the third party administrator.

Consult CAGI website for a list of participants in the third party verification program: www.cagi.org

- NOTES:
- a. Measured at the discharge terminal point of the compressor package in accordance with ISO 1217, Annex C; ACFM is actual cubic feet per minute at inlet conditions.
 - b. The operating pressure at which the Capacity (Item 3) and Electrical Consumption (Item 11) were measured for this data sheet.
 - c. Maximum pressure attainable at full flow, usually the unload pressure setting for load/no load control or the maximum pressure attainable before capacity control begins. May require additional power.
 - d. Total package input power at other than reported operating points will vary with control strategy.
 - e. Tolerance is specified in ISO 1217, Annex C, as shown in table below:

Member:



| Volume Flow Rate at specified conditions | | Volume Flow Rate | Specific Energy Consumption | No Load / Zero Flow Power |
|--|-----------------------|------------------|-----------------------------|---------------------------|
| m ³ / min | ft ³ / min | % | % | |
| Below 0.5 | Below 15 | +/- 7 | +/- 8 | +/- 10% |
| 0.5 to 1.5 | 15 to 50 | +/- 6 | +/- 7 | |
| 1.5 to 15 | 50 to 500 | +/- 5 | +/- 6 | |
| Above 15 | Above 500 | +/- 4 | +/- 5 | |

ROT 030

COMPRESSOR DATA SHEET

CAP710-NXHE132-175

Rotary Compressor: Fixed Speed

| MODEL DATA - FOR COMPRESSED AIR | | | |
|---------------------------------|--|---------------------------------------|-------------------------|
| 1 | Manufacturer: FS Curtis | | |
| 2 | Model Number: NxHE132A-175 | | Date: 6/19/2018 |
| | <input checked="" type="checkbox"/> Air-cooled | <input type="checkbox"/> Water-cooled | Type: Screw |
| | <input checked="" type="checkbox"/> Oil-injected | <input type="checkbox"/> Oil-free | # of Stages: 2 |
| 3* | Rated Capacity at Full Load Operating Pressure ^{a, e} | 738.4 | acfm ^{a, e} |
| 4 | Full Load Operating Pressure ^b | 175 | psig ^b |
| 5 | Maximum Full Flow Operating Pressure ^c | 176 | psig ^c |
| 6 | Drive Motor Nominal Rating | 180 | hp |
| 7 | Drive Motor Nominal Efficiency | 96.2 | percent |
| 8 | Fan Motor Nominal Rating (if applicable) | 5.5 | hp |
| 9 | Fan Motor Nominal Efficiency | 89.5 | percent |
| 10* | Total Package Input Power at Zero Flow ^e | 65.1 | kW ^e |
| 11 | Total Package Input Power at Rated Capacity and Full Load Operating Pressure ^d | 156.7 | kW ^d |
| 12* | Specific Package Input Power at Rated Capacity and Full Load Operating Pressure ^e | 21.2 | kW/100 cfm ^e |

*For models that are tested in the CAGI Performance Verification Program, these items are verified by the third party administrator.

Consult CAGI website for a list of participants in the third party verification program: www.cagi.org

- NOTES:
- a. Measured at the discharge terminal point of the compressor package in accordance with ISO 1217, Annex C; ACFM is actual cubic feet per minute at inlet conditions.
 - b. The operating pressure at which the Capacity (Item 3) and Electrical Consumption (Item 11) were measured for this data sheet.
 - c. Maximum pressure attainable at full flow, usually the unload pressure setting for load/no load control or the maximum pressure attainable before capacity control begins. May require additional power.
 - d. Total package input power at other than reported operating points will vary with control strategy.
 - e. Tolerance is specified in ISO 1217, Annex C, as shown in table below:

Member:



| Volume Flow Rate at specified conditions | | Volume Flow Rate | Specific Energy Consumption | No Load / Zero Flow Power |
|--|-----------------------|------------------|-----------------------------|---------------------------|
| m ³ / min | ft ³ / min | % | % | |
| Below 0.5 | Below 15 | +/- 7 | +/- 8 | +/- 10% |
| 0.5 to 1.5 | 15 to 50 | +/- 6 | +/- 7 | |
| 1.5 to 15 | 50 to 500 | +/- 5 | +/- 6 | |
| Above 15 | Above 500 | +/- 4 | +/- 5 | |

ROT 030